



PAR-KUT INTERNATIONAL, INC.

40961 Production Drive • Harrison Twp., Michigan 48045-1351
Telephone: (586) 468-2947 • Fax: (586) 463-6059
www.parkut.com e-mail: sales@parkut.com
Portable Steel Buildings since 1954.

4' x 6' Standard Booth 2-5 Week Delivery Available!

This is a single unit welded galvanized steel construction standard booth ready for immediate delivery. Installation of this 1400# booth can be accomplished with a forklift or by utilizing the lift ring mounted in the roof. Completely fabricated and "Operational Ready" after power is connected, fed through the floor and connected directly to CB box.

Details:

- Single Unit Welded Galvanized Steel Construction.
- 3" Canopy overhang with a 6" Fascia on all sides.
- Glazing is clear safety tempered glass all set in clear anodized aluminum frames.
- Ventilation windows with screens included.
- Booth painted single color of choice from standard Par-Kut color charts.
- 25" wide sliding Steel door with painted kick panel, weather-stripping, ball bearing hangers, safety glazing, heavy-duty track, hook bolt lock & hardware.
- 18" Deep painted galvanized steel counter, with painted storage drawer.
- Fluorescent Light – 24" - 17w with integral switch, lamp included.
- Duplex Outlet – Mounted below the counter.
- 120v / 1500w Surface mounted Heater with integral thermostat.
- Standard 100Amp 12-space circuit breaker panel with main breaker is included.

\$ 6,175.00 (Add Sales Tax & Freight)

OPTIONAL ADD-ON ACCESSORIES:

- ADD \$ 340.- For tinted glazing upgrade, Gray or Bronze available.
- ADD \$ 165.- To Upgrade Standard 1500w Heater to a larger 4Kw Model.
- ADD \$ 1,120.- To replace standard heater with 11,600 BTU Combo Heat / Air Conditioner Unit with integral thermostat, mounted through the wall.
- ADD \$ 160.- For a cashier windows in the door.
- ADD \$ 325.- For a cashier window mounted in the wall opposite of the door (Roller Style).
- ADD \$ 153.- For a lay-in Anti Fatigue mat.